

15-193-20009-0000

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GIAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED
DEC 1 1 1968
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Tilco, Et al,

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Ostmeyer Well No. 1

Location: CSW-SE Sec. 1 Twp. 10 Rge. (E)(W) 31

County: Thomas Total Depth 4265 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1700'.

Circulate hole with heavy mud. Pull DP to 1850' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent