

15-179-20303-0000

Form CP-3
Rev. 6-4-68

KANSAS

24

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Ziegler Well No. 1

Location SE-NW-NE Sec. 3 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4076'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:15 PM Day 22 Month 3 Year 1972

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225' to 900'. Pulled DP to 210' and displaced 30 Cu. Ft. cement thru
DP from 210' to 135'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Pichek
Well Plugging Supervisor

INVOICED
DATE 3-24-72
INV. NO. 5413-02