

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,
Complete Address Box #352, Russell, Kansas.
Lease Name Custer Well No. 3
Location SE-SW-SE Sec. 12 Twp. 10 Rge. (E) (W) 26
County Sheridan Total Depth 4090'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 4:30 AM Day 14 Month 7 Year 1973

The above well was plugged as follows:

204'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
from 1275' to 950'. Pulled DP to 215' and displaced 30 Cu. Ft. cement from 215' to
140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickels
Well Plugging Supervisor

INVOICED

DATE 7/16/73
INV. NO. 9639-W