

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-1-1963
OCT 1 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kimbark Exploration Company,

Complete Address: 201 University Blvd., Denver, Colorado.

Lease Name Von Lintel Well No. 1

Location SW-SW-NE Sec. 2 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4330

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.,

Address: Box # 405, Chase, Kansas. License No. 436

Operation Completed: Hour 3:15PM Day 26 Month 9 Year 1963

The Above well was plugged as follows:

198'--8 5/8" Surface pipe, cement circulated with 265 sx.
4075'--4 1/2" set with 600 gal. Latex. Squeezed @ 2000' with 260 Sx cement.

Sanded well back to 3875' and set 3 Sx cement with dump bailer. Set plug
and 20' rock bridge @ 1570' and 3 Sx cement with dump bailer. Pulled 4 1/2"
to 550', circulated heavy gel mud (17 Sx.) and displaced 20 Sx cement
thru 4 1/2". Pulled 4 1/2" to 210' and displaced 20 Sx cement thru 4 1/2". Pulled
4 1/2", set bridge @ 30' and 10 Sx cement to bottom of cellar.

(Cementing and mudding operations performed by Globe Oil Well Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 10/2/63

INV. NO. 7832-W