

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
8-23-1972
AUG 23 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Von Lintel Well No. 1

Location NE-SW-NE Sec. 2 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 3895'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 3:15 PM Day 17 Month 8 Year 1972

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 290 Sx. (Lost circulation @ 100', pipe was circulated from the top down the side.)

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 95 Cu. Ft. cement thru DP from 1250' to 960'. Pulled DP to 205' and displaced 30 Cu. Ft. cement thru DP from 205' to 130'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Deibel
Well Plugging Supervisor

INVOICED

DATE 8/23/72
INV. NO. 6216-W