

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
11-20-1972
NOV 20 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Von Lintel Well No. 2
Location NE-NE-NE Sec. 2 Twp. 10 Rge. (E) (W)26
County Sheridan Total Depth 4282'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.

Operation Completed: Hour 10:00 AM Day 17 Month 11 Year 1972

The above well was plugged as follows:

190'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dinkel
Well Plugging Supervisor

DATE 11/20/72
INV. NO. 6654-W