

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

DEC 5 1967

12-5-67  
CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202Well Plugging Authority,  
issued November 30, 1967.

Operator's Full Name Sam P. Wallingford, Inc., Oil & Gas Division

Complete Address: 304 Colorado Derby Bldg., Wichita, Kansas 67202

Lease Name Cornwell Well No. # 1

Location C W/2 SE NW Sec. 3 Twp. 24 Rge. 15 (E) W

County Stafford Total Depth 4115'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas 67530 License No. 574

Operation Completed: Hour 11:45 AM Day 4th Month December Year 1967

## The Above well was plugged as follows:

276' of 8 5/8" surface pipe, cement circulated. 4115' of 4 1/2" long string, cemented with 110 sacks. Plug back T.D. 4060'. Top perforation 4040'. Bottom of the hole was sanded to 4000', and cemented with 4 sacks, through the dump bailer, with cement from 4000' to 3950'. 2500' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 260', bridge plug and rock bridge from 260' to 250'. 10 sacks of cement was mixed in a barrel, and put on plug at 250', through the dump bailer, and let set over week-end. Hole was bailed dry, and 15 sacks of cement was added to the plug, with cement from 250' to 175'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging SupervisorRECEIVED  
DEC 12/5/67  
INV. NO. 6818-4