

15-033-20361-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Box Ranch "A" Well No. 2

Location SE SE Sec. 9 Twp. 35S Rge. 20 (E)    (W) X

County Comanche Total Depth 5740

Abandoned Oil Well    Gas Well X Input Well    SWD Well    D & A   

Other well as hereafter indicated   

Plugging Contractor Clarke Corp.

Address 107 W. Foulmer, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 1 Pm. Day 16 Month 9 Year 1980

The above well was plugged as follows:

640' 8 5/8" casing w/450 sax cement. 4 1/2" casing set at 5730' w/100  
sax cement. Top pref's at 5626-33'. Sand back to 5600'-Top sand w/4  
sax cement w/dump bailer-Pull 4950' casing-Allied mixed & pumped 8  
sax hulls-25 sax gel-150 sax 50/50 posmix cement w/4% gel & 3% cc  
in 8 5/8" casing to top of casing. Shut in w/100# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 9-18-80  
INV. NO. 3170W

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 18 1980  
CONSERVATION DIVISION  
Wichita, Kansas