

RECEIVED  
STATE CORPORATION COMMISSION

15-033-20264-0000 f

MAR 27 1979

KANSAS

Form CP-3  
Rev. 6-4-68

CONSERVATION DIVISION  
Wichita, Kansas

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W-Douglas Suite 300, Wichita, Ks. 67202

Lease Name Box Ranch "A" Well No. 1

Location SE SE SW Sec. 9 Twp. 35 Rge. 20 (E)    (W) X

County Comanche Total Depth 5780

Abandoned Oil Well    Gas Well X Input Well    SWD Well    D & A   

Other well as hereafter indicated   

Plugging Contractor Pratt Well Service.

Address 723 S. Ninnescah, Pratt Ks. 67124 License No. 761

Operation Completed: Hour 1 Pm. Day 20 Month 3 Year 1979

The above well was plugged as follows:

577' 8 5/8" casing w/ 450 sax cement. 2 7/8" casing set @ 5776'-plug  
back to 5744'-Top perforation @ 5648'-Set permanent steel bridge-  
plug @ 5510' Shot casing off @ 3816'- Howco mixed & pumped 25 sax-  
cement in 7 7/8" hole. Pull 3816' 2 7/8" casing. Howco mixed @ pumped  
5 sax hulls-20 sax gel-125 sax 50/50 posmix cement w/6% gel to top of  
casing. Shut in w/ "0" pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3-28-79  
INV. NO. 9317-LJ