

15-033-00107-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Earl M. Knighton

Complete Address 900 Sutton Place Wichita, KS

Lease Name J.E. Alexander Well No. 1

Location C NE/NW Sec. 4 Twp 35s Rge. 20 (E) (W) W

County Comanche Total Depth 5595

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1182 Great Bend, KS License No. 623

Operation Completed: Hour 9:00 AM Day 21 Month 3 Year 1973

The above well was plugged as follows:

612 ft 8 5/8 surface cemented with 400 sacks. 5594 ft 4 1/2 long string  
cemented with 170 sacks. Top perf. 5455 ft. Sand to 5400 ft, 4  
sacks cement with bailer. Pulled 4000 ft 4 1/2. Set 10 ft rock bridge  
at 250 ft with 25 sacks cement. Mud to 40 ft, 10 ft rock bridge ,  
10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. Russell Biberstein  
Well Plugging Supervisor

DATE 3-23-73

INV. NO. 7161-4