

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-041-20017-00-02
Spot: NWSESE Sec/Twnshp/Rge: 34-16S-4E
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: DAETWILER Well #: 1
County: DICKINSON Total Vertical Depth: 2354 feet

Operator License No.: 33005
Op Name: RANDON PRODUCTION COMPANY IN
Address: 2761 REMINGTON RD
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	124		70 SX
PROD	5.5	2317		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2010 9:00 AM
Plug Co. License No.: 33005 Plug Co. Name: RANDON PRODUCTION COMPANY INC.
Proposal Rcvd. from: RANDY SVITAK Company: RANDON PRODUCTION Phone: (620) 924-5437

Proposed Plugging Method: SAND BOTTOM TO 50' ABOVE TOP PERFS OR OPEN HOLE (2267) CAP WITH 5 SXS CEMENT. CIRCULATE WITH CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 04/07/2010 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Perfs:

SANDED BOTTOM TO 2150' AND CAPPED WITH 5 SXS CEMENT. PULLED 500' OF CASING. RAN TUBING AND CIRCULATED WITH (125 SXS) CEMENT FROM 250' TO SURFACE.

INVOICED
DATE 5/04/10
INV. NO. 2010010276

Remarks: 125 SXS CEMENT = TOTAL CEMENT MIXED PER SACK BY RANDON'S CEMENT MIXER

Plugged through: TBG

District: 02

Signed

Judd Klock - DISTRICT SUPERVISOR
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

APR 20 2010

CONSERVATION DIVISION
WICHITA, KS