

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21135-00-00
Spot: SENENWSE Sec/Twnshp/Rge: 26-17S-4E
2002 feet from S Section Line, 1335 feet from E Section Line
Lease Name: PAGENKOPF Well #: 2
County: MARION Total Vertical Depth: 2365 feet

Operator License No.: 33005
Op Name: RANDON PRODUCTION COMPANY IN
Address: 2761 REMINGTON RD
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		150 SX
PROD	4.5	2364	880	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2010 12:00 PM
Plug Co. License No.: 33005 Plug Co. Name: RANDON PRODUCTION COMPANY INC.
Proposal Rcvd. from: RANDY SVITAK Company: RANDON PRODUCTION Phone: (620) 381-1856

Proposed Plugging Method: SAND BOTTOM TO 50' ABOVE TOP PERF (2262) CAP W/4SX CEMENT. SHOOT PIPE AND PULL ALL WE CAN. CEMENT TOP FROM 50' BELOW BOTTOM OF SURFACE (258')

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 04/13/2010 11:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

4/11-12/10 RANDON MOVED IN SANDED OFF BOTTOM. THEY TAGGED SAND AT 2215' AND CAPPED W/4SXS CEMENT. THEY SHOT OFF CASING AND PULLED CASING FROM 880'. 4/12/2010 RANDON CALLED IN PLAN TO DUE TOP PLUG ON 4/13/2010 BEFORE NOON. 4/13/2010 I ARRIVED ON SITE AT 9:45 AM. RANDON HAD RUN 2" TUBING TO 256'. RANDON ALREADY MIXED CEMENT AND FLYASH. RANDON MIXED APPROX 43 SXS CEMENT @ 94 LBS EACH AND 32 SX FLYASH @ 80 LBS EACH. THEY CIRCULATED CEMENT TO SURFACE. I QUESTIONED WHY IT ONLY TOOK 75 SXS TO CIRCULATE TO SURFACE. IT WAS LATER DETERMINED THEY HAD MIXED CEMENT WETTER THAN USUAL. TALKED TO RANDY ABOUT TOP PLUG PROBABLY GOING TO FALL SOME WHAT, AND THAT THEY WILL PROBABLY NEED MORE CEMENT TO CAP THE WELL. 4/14/2010 I CHECKED TOP PLUG THIS MORNING, AND FOUND IT TO BE APPROX 60' DOWN. NO FLUID ON TOP OF PLUG. I NOTIFIED RANDY ABOUT HOW FAR THE PLUG WAS DOWN. RANDY SAID. HE WOULD TOP IT OFF AFTER HE PLUGS THE REST OF THE WELLS ON THE COMPLIANCE AGREEMENT.

Perfs:

Top	Bot	Thru	Comments
2312	2322	CSG	

INVOICED
DATE 5/04/10
INV. NO. 200010276

Remarks:

Plugged through:

District: 02

Signed _____

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

APR 20 2010 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

JK