

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21663-00-00
Spot: SESE Sec/Twnshp/Rge: 15-30S-19W
660 feet from S Section Line, 575 feet from E Section Line
Lease Name: SEALEY Well #: 15-16
County: KIOWA Total Vertical Depth: 5300 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, INC.
Address: 6001 NW 23RD ST
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.38	266		WITH 250 SX CMT
COND	20	55		WITH 6 YDS CMT
PROD	4.5	5300	2488	WITH 275 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/08/2010 11:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DAVID HICKMAN Company: REDLAND RESOURCES Phone: (580) 334-7013

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2010 12:35 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

4/8/10: 1ST PLUG SAND TO 5025' & 4 SX CMT. 2ND PLUG PUMPED 160 BBLS WATER, 15 SX GEL, & 50 SX CMT TO 1200'. NO RETURNS. 4/9/10: 3RD PLUG PULL CASING TO 600' & PUMP 40 SX CMT. NO RETURNS. SDON. 4/9/10: 4TH PLUG TAG CMT @ 443'. PULL CASING TO 288'. PUMP 500# HULLS, 25 SX GEL, & 40 SX CMT. NO RETURNS. PULL CASING. WAIT ON CMT 30 MINUTES. RUN CASING. NO TOC. 5TH PLUG PUMP 50 SX CMT @ 288'. NO RETURNS. 6TH PLUG RE-RAN CASING TO 288'. PUMPED 60 SX CMT. NO RETURNS. SDFW. 4/12/10: 7TH PLUG TAGGED TOC @ 270'. RAN 4 1/2" TO 270'. PUMPED 25 SX GEL & 75 SX COMMON CMT W/2% CC. GOOD RETURNS. 8TH PLUG PULLED CASING TO 40' & PUMPED 75 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5100	5110		
5076	5086		

INVOICED

DATE 5/04/10
INV. NO. 2010010278

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
APR 15 2010
KCC DODGE CITY

RECEIVED
APR 21 2010
KCC WICHITA

Form CP-210