

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-22095-00-00  
Spot: S2NWNW Sec/Twnshp/Rge: 6-17S-30W  
915 feet from N Section Line, 515 feet from W Section Line  
Lease Name: BROOKS 6B Well #: 1  
County: LANE Total Vertical Depth: 4660 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209		WITH 150 SX CMT
PC		2271		WITH 490 SX CMT
PROD	4.5	4659	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2010 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/09/2010 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT & 300# HULLS. GEL SPACER TO 2700'. PUMP 185 SX CMT FROM 2700' TO 0'. PRESSURE TO 750#. HOLDING AT 200#. PUMP 5 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
4560	4564		CONG. SAND
4545	4548		JOHNSON
4534	4536		JOHNSON
4035	4039		LKC - E
3983	3986		LKC - C


INVOICED  
DATE 5/04/10  
INV. NO. 20100102.79

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

APR 16 2010

KCC DODGE CITY

RECEIVED

APR 21 2010

KCC WICHITA