

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25230-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 8-17S-12W
1830 feet from N Section Line, 2030 feet from W Section Line
Lease Name: DEMEL Well #: 1-8
County: BARTON Total Vertical Depth: 3493 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	778	0	575 SX
PROD	5.5	3489	2510	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2010 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GERALD ACHATZ Company: SAMUEL GARY JR. & ASSOCIATES Phone: (303) 831-4673

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom - topped with 5 sxs cement.
Cut casing at 2510' - pulled casing to 1550' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 817' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 450' - pumped 40 sxs cement.
Pulled casing to 200' - circulated cement to surface with 60 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3383	3386		

INVOICED
DATE: 5/24/10
INV. NO. 2010010281

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36670.

Plugged through: DP

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2010

Form CP-2/3

APR 14 2010


CONSERVATION DIVISION
WICHITA, KS

WILLIAM S. HUTCHINSON
P. O. BOX 642
DERBY, KS 67037

#1-8 DEMEL

8-17-12W
SW SE NW

CONTR DAMAC DRILLING, INC. CTY BARTON
GEOLOGICAL FIELD SUNFLOWER EXT (1/4 N)



ELV 1928 KB SPD 4/26/84 CARD ISSUED 8/2/84 IP P 50 BO & 5 BWPD
1920 GL ARB 3399-3404

LOG	Tops	Depth/Datum
ANH	809+1119
LANS	3147-1219
ARB	3394-1466
PBTD	3404-1476
RTD	3460-1532

API 15-009-23,505

8 5/8 " 810/350SX, 5 1/2 " 3459/150SX
DST (1) 3360-3406 (LKC) / 30-45-60-45, SB, REC 2430' CO,
420' MDY OIL, SIP 1134-113#, FP 321-771 / 867-1081#
MICT - CO, PF (ARB) 3399-3404 W/4 SPF, SWB DWN, GSO, NAT,
POP, P 50 BO & 5 BWPD (GR 32°), 5/17/84

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS