

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25971-00-00
Spot: E2NWSES Sec/Twnshp/Rge: 13-15S-17W
990 feet from S Section Line, 1755 feet from W Section Line
Lease Name: VONFELDT Well #: 2-13
County: ELLIS Total Vertical Depth: 3670 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1094		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/26/2010 3:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: FRANK ROME Company: SAMUEL GARY JR. & ASSOCIATES Phone: (303) 831-4673

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 04/26/2010 3:45 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3540' w/25 sxs.
2nd. Plug at 1150' w/40 sxs.
3rd. Plug at 460' w/100 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 5/04/10
INV. NO. 2010010281

RECEIVED
MAY 03 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Luca D. Booye

(TECHNICIAN)

CM

APR 27 2010