

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15753-00-00
Spot: SWNENE Sec/Twnshp/Rge: 12-16S-12W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: WOYDZIAK Well #: 5
County: BARTON Total Vertical Depth: 3323 feet

Operator License No.: 6357
Op Name: WEBCO OIL CO., INC.
Address: 2136 NE 90 AVE
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	776	0	w/unknown sxs cmt
PROD	5.5	3319	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2010 1:00 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: ALAN Company: WEBCO OIL CO., INC. Phone: (785) 483-1676

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 1550' - 750' - 250'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2010 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2300' - pumped 100 sxs cement - followed with 160 sxs cement with 500# hulls mixed in - cement circulated.
POOH. Hooked up to casing and pumped 25 sxs cement.
Max. P.S.I. 200#.
Hooked up to Braden head and pumped 55 sxs cement.
Max. P.S.I. 200#. S.I.P. 175#.

INVOICED
DATE 5/04/10
INV. NO. 2010010286

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3815.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

APR 26 2010

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

APR 21 2010

PHILLIPS PETROLEUM CO.

#5 WYDZIAK

12-16-12W
SW NE NE

Contr. _____ BARTON _____ County

E1888 Comm. _____ Comp. 8-11-50 IP 2564 BOPD
DRAW DOWN

Tops	Depth	Datum
HEEB	2912	1054
BR LM	3028	1140
LANS	3045	1157
ARB	3318	1430
T&D.	3323	1435

Casing

8" 776 SWB 67 B0/1 HR
5" 3319

KRAFT-PRUSA POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS