

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21513-00-00
Spot: SESWSE Sec/Twnshp/Rge: 36-26S-33W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: STANDLEY Well #: 1-36
County: FINNEY Total Vertical Depth: 5400 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1960		
CIBP		4920		WITH 2 SX CMT
SURF	8.625	1920		575 SX
DVT		3016		WITH 200 SX CMT
PROD	5.5	5125	1942	350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2010 8:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (785) 623-1066

Proposed Plugging Method: CIBP @ 4950'. PLUG AT 1940' WITH 50 SX CMT. PLUG AT 950' WITH 40 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2010 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4920' WITH 2 SX CMT. (ATTEMPT TO LOAD HOLE. WOULD NOT LOAD)
CIBP @ 1960'. LOAD HOLE. HOLDING. 1ST PLUG AT 1940' WITH 50 SX CMT. 2ND PLUG AT 955' WITH 40 SX CMT. 3RD PLUG AT 408' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4991	4996		MORROW SAND
4981	4981		ATOKA SAND

INVOICED
DATE 4/28/10
INV. NO. 2010010226

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: CSG

District: 01

RECEIVED

APR 16 2010

KCC DODGE CITY

Signed

Ken Jehlik

RECEIVED

(TECHNICIAN)

APR 21 2010

KCC WICHITA