

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22531-00-00  
Spot: W2NWNESW Sec/Twnshp/Rge: 16-18S-25W  
2310 feet from S Section Line, 1485 feet from W Section Line  
Lease Name: ELMORE RYAN Well #: 1  
County: NESS Total Vertical Depth: 4504 feet

Operator License No.: 30269  
Op Name: ARGENT ENERGY, INC.  
Address: 1313 N WEBB RD STE 210  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	255		WITH 200 SX CMT
DVT		1804		WITH 350 SX CMT
PROD	4.5	4477	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2010 10:30 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: BRAD SEIB Company: ARGENT ENERGY Phone: (785) 798-3988

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 25 SX CMT & 100# HULLS. PULL TBG TO 1800' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/30/2010 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4390' & PUMP 25 SX CMT WITH 100# HULLS. PULL TBG TO 1800' & PUMP 115 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 35 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4477	4504		

INVOICED  
DATE 4/22/10  
INV. NO. 2010010185

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 16 2010

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
APR - 5 2010  
KCC DODGE CITY

Form CP 73