

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22817-00-00
Spot: N2S2N2SW Sec/Twnshp/Rge: 16-18S-25W
1800 feet from S Section Line, 1350 feet from W Section Line
Lease Name: ELMORE RYAN ETAL Well #: 2
County: NESS Total Vertical Depth: 4489 feet

Operator License No.: 30269
Op Name: ARGENT ENERGY, INC.
Address: 1313 N WEBB RD STE 210
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	254		WITH 150 SX CMT
PROD	4.5	4481	0	WITH 1000 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2010 10:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: BRAD SEIB Company: ARGENT ENERGY Phone: (785) 798-3988

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 25 SX CMT & 100# HULLS. PULL TBG TO 1800' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2010 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4360' & PUMP 25 SX CMT WITH 100# HULLS. PULL TBG TO 1800' & PUMP 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 35 SX CMT. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4481	4489		

INVOICED
DATE 4/22/10
INV. NO. 2010010185

RECEIVED
KANSAS CORPORATION COMMISSION

APR 16 2010

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
APR - 5 2010
KCC DODGE CITY

FORM CP-223