

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20514-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 18-4S-21W
390 feet from S Section Line, 2210 feet from E Section Line
Lease Name: NUTTYCOMB TRUST Well #: 1-18
County: NORTON Total Vertical Depth: 3820 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/31/2010 7:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 03/31/2010 8:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3632' w/25 sxs.
2nd. Plug at 1864' w/25 sxs.
3rd. Plug at 1107' w/100 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 4/22/10
INV. NO. 2010010186

Remarks: SWIFT CEMENTING COMPANY

Plugged through: DP

District: 04

Signed _____

RECEIVED

CM

APR 12 2010

Form CP-2/3

KCC WICHITA

APR 07 2010