

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25026-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 36-16S-24W  
2210 feet from S Section Line, 860 feet from W Section Line  
Lease Name: MISHLER Well #: 1  
County: NESS Total Vertical Depth: 4550 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		WITH 150 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2010 3:30 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1900' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 04/05/2010 5:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1900' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED  
DATE 4/22/10  
INV. NO. 2010010188

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 16 2010

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

*Michael Maier*  
(TECHNICIAN)

RECEIVED

APR - 7 2010

KCC DODGE CITY

Form CD 2/3