

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-19004-00-00  
Spot: SESENW Sec/Twnshp/Rge: 1-12S-23W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: NEWCOMER Well #: 5  
County: TREGO Total Vertical Depth: 3843 feet

Operator License No.: 33263  
Op Name: BOWMAN, WILLIAM F. DBA THE BILL  
Address: 2640 W RD  
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	330	0	225 SX
PROD	4.5	3835	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/07/2010 10:00 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: WILLIAM "BILL" BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 885-4830

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
PBTB 3760'. Perf at 1046' - 1890' - 2350'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/07/2010 1:00 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Ran tubing to 3329' - pumped 150 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1859' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls -  
circulated to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 10 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 40 sxs 60/40 pozmix - 4% gel.  
S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
3727	3731		
3695	3698		
3654	3662		

INVOICEL  
DATE 4/22/10  
INV. NO. 2010010190

Remarks: LEASE ORIGINALLY KNOWN AS LOSEE #5. ALLIED CEMENTING COMPANY-TICKET #39163.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 19 2010

CONSERVATION DIVISION  
WICHITA, KS

APR 14 2010


TEXACO INC. #5 LOSEE 1-12-23W SE SE NW

Contr. LEBEN DRILLING CO. TREGO County

E 2421KB Comm. 3/4/63 Comp. 4/11/63 IP. PMP 93 BOPD + 8 BWPD GR 39.7/LANS 3654-

LOG Tops	Depth	Datum
HEEB	3620	-1199
TOR	3638	-1217
LANS	3653	-1232
'B' ZONE	3695	-1274
'D' ZONE	3707	-1286
'F' ZONE	3727	-1306
'J' ZONE	3815	-1394
RTD	3843	-1422

Casing  
 8" 330:  
 4" 3835/100 SX:  
 NO TESTS:  
 CO 3843 TD: SWB 3 1/2 GMW/2 HRS:  
 GRN LOG: 12/3815-19: SWB O/S  
 + 2 GW/2 HRS: 12/3727-31: SWB  
 O/S + 6 1/2 GW/3 HRS: A 3000: SWB  
 55 BO + 50 B L WTR/8 HRS: 9/  
 3695-98: 24/3654-62: PB 3760:  
 A 2000: SWB LD: SWB 82 BO +  
 21 BW/8 HRS: POP:  
 PMP 43 BO + 8 BWPD:



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS