

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1972
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this
date requested permission to plug the following described well:Mr. Bucheister guarantees payment of the plugging fee.Operator's full Name: John O. Farmer, Incorporated,Complete Address: 370 West Wichita Avenue, Russell, Kansas.Lease Name: Ziegler Well No. 1Location: SE-NW-NE Sec. 3 Twp. 10 Rge. (E)(W) 26County: Sheridan Total Depth 4076' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Bucheister was instructed to plug the well as follows:202'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1000'.Circulate hole with heavy mud. Pull DP to 1225' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 210' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent