

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 18 1967
05-18-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Leo Dreiling of Leo J. Dreiling Oil Co., has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Mader Well No. 1

Location: NW-NW-NE Sec. 12 Twp. 10 Rge. (E)(W) 26

County Sheridan Total Depth 4034 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

- 197'--3 5/8" Surface pipe, cement circulated with 150 Sx.
- Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.
- " " 180' and 20 Sx. cement.
- " " 40' with 1/8 sk. hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent