



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 10-1-1963
 OCT 1 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Herman Fellhoelter of Kimbark Exploration Co., has this date requested permission to plug the following described well:

Mr. Fellhoelter guarantees payment of the plugging fee.

Operator's full Name: Kimbark Exploration Company,

Complete Address: 201 University Blvd., Denver, Colorado.

Lease Name: Von Lintel Well No. 1

Location: SW-SW-NE Sec. 2 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4330 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Fellhoelter was instructed to plug the well as follows:

198'--8 5/8" surface pipe, cement circulated with 265 Sx.
4075'--4 1/2" set with 600 gal. Latex. Squeezed @ 2000' with
260 Sx cement.

Sand well back to 3875' and set 3 Sx cement with dump bailer.
Set plug and 20' rock bridge @ 1570' and 3 Sx cement with dump
bailer. Pull 4 1/2" to 550', circulate heavy gel mud and displace
20 Sx. cement thru 4 1/2". Pull casing to 210' and displace 20 Sx.
cement thru 4 1/2". Pull 4 1/2" set bridge and 10 Sx cement to
bottom of cellar.

Very truly yours,

H. L. Nichols
 Conservation Division Agent