

State of Kansas



15-195-20054-00-00

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

DEC 6 1967  
12-06-1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: Bender Well No. 1

Location: SW NW-NE-SE ANB KCC Sec. 10 Twp. 12 Rge. (E)(W) 23

County Trego Total Depth 1945 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

160'--8 5/8" Surface pipe, cement circulated with 125 Sx.  
Dakota section from 1000' to 1190'.

Circulate hole with heavy mud. Pull DP to 1210' and displace 100 Sx.  
cement thru DP. Pull DP to 180' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

Conservation Division Agent