

15-129-10105-00-01

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Woolridge of Amoco has this

date requested permission to plug the following described well:

Mr. Woolridge guarantees payment of the plugging fee.

Operator's full Name: Amoco Production Company

Complete Address: Box 432, Liberal, Kansas

Lease Name: Cowen Gas Unit "B" Well No. 1

Location: G W/2 W/2 SE NE Sec. 34 Twp. 31 Rge. 40 (E) (W)

County: Forton Total Depth 6050' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Woolridge was instructed to plug the well as follows:

8 5/8" to 714' circulated w/ cement. 5 1/2" to 5845' cemented.

Top perforations 3517' Plug bottom w/ Bridge Plug & 7 sacks cement.

Top of cement 3630' Mud 3630' to 1400'

Spot 20 sacks cement 1400' to 1350' Mud 1350' to 765'

Spot 35 sacks cement 765' to 665' Mud 665' to 40'

Plug, Muller & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent