



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

13 May 1982

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-033-20,559-0000

Dear Sir:

Mr. Martin Riedl of Lawson Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Donald C. Lawson Oil Producer

Complete Address 200 Douglas Bldg. Broadway Douglas Wichita Kansas 67202

Lease Name: Boy Ranch Well No. A1

Location: C-5/2-SW Sec. 3 Twp. 35 Rge. 20 (E) (W)

County: Comanche Total Depth: 5,595'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Riedl was instructed to plug the well as follows:

The cement circulated 667' of 8 5/8" surface casing. The 1st plug at 1080' with 60 bbl of cement. 2nd plug at 680' with 40 bbl of cement. 3rd plug at 40' to 0' on solid bridge with 10 bbl of cement. Then they circulated 10 bbl of cement in rat hole & 5 bbl of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by  
Very truly yours,

Halliburton Co.

RECEIVED  
STATE CORPORATION COMMISSION  
5-18-82  
MAY 18 1982

Paul A. Luthi  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas