

RECEIVED
6-27-2003
JUN 27 2003
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-033-20833 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Roberts and Murphy, Inc. KCC LICENSE # 4145
(owner/company name) (operator's)

ADDRESS Post Office Box 7125 CITY Shreveport

STATE Louisiana ZIP CODE 71137-7125 CONTACT PHONE # (318) 221-8601

LEASE Petty WELL# 2-27 SEC. 27 T. 34S R. 20W (East/West)

NW - SE - SE - SPOT LOCATION/OOOO COUNTY Comanche

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1000 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL 1 GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT 80 CEMENTED WITH SACKS

SURFACE CASING SIZE 10 5/8" SET AT 650 CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 6436 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 6174-6184', 6188-6198'

ELEVATION 1720/1731 T.D. 6500 PBDT 6436 ANHYDRITE DEPTH 5320
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD x POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @6100' and dump bail 25 sks cement, cut 4 1/2" casing @ 5750' and pull csg. Pump down 10 5/8" csg; 300# Hulls; 10 sks gel; 50 sks cmt; 10 sks gel; 100# Hulls; 150 sks cmt. Dump down 10 5/8" csg surf. 10' cmt.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? Log previously submitted

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Frazier PHONE# (318) 458-2911

ADDRESS Post Office Box 7125 City/State Shreveport, LA 71137-7125

PLUGGING CONTRACTOR Key Energy Services KCC LICENSE # 33223
(company name) (contractor's)

ADDRESS P.O. Box 1273, Liberal, KS 67905-1273 PHONE # () 620-624-7235

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Rig availability, will notify KCC of date

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6/24/03 AUTHORIZED OPERATOR/AGENT: Bruce L. Robert
(signature)

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Roberts and Murphy, Inc.
PO Box 7125
1500 N. Market
Shreveport, LA 71137-7125

June 27, 2003

Re: PETTY #2-27
API 15-033-20833-00-00
NWSESE 27-34S-20W, 660 FSL 1000 FEL
COMANCHE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888