

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Form 67-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and file ONE Copy)

API # 15-033-20774 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Roberts and Murphy, Inc. KCC LICENSE # 4145
(owner/company name) (operator's)

ADDRESS PO Box 7125 CITY Shreveport

STATE LA ZIP CODE 71137-7125 CONTACT PHONE # (318) 221-8601

LEASE Petty WELLS# 1-27 SEC. 27 T. 34S R. 20 (~~East~~/West)

- - SW - SE SPOT LOCATION/QCCC COUNTY Comanche

660 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

2300 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL X D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE 20" SET AT 80' CEMENTED WITH 150 SACKS

SURFACE CASING SIZE 8 5/8" SET AT 651' CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 6500' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 6218'-34', CIBP @ 6150', 5012'-21'

ELEVATION 1732'/1743' T.D. 6500' PSTD 6370' ANHYDRITE DEPTH 2015'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ ±5000 and dump bail two sxs cmt. Cut casing and pull. Pump from surface 50 sxs cmt, 8 5/8 plug and 100 sxs cmt.

(if additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? Logs previously submitted

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. Ken Frazier PHONE# (318) 425-4223
C/O Roberts and Murphy, Inc.
ADDRESS P.O. Box 7125 City/State Shreveport, LA 71137-7125

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893
(company name) (contractor's)

ADDRESS PO Box 847, Pratt, KS 67124 PHONE # (316) 672-5901

PROPOSED DATE AND HOUR OF PLUGGING (if known?) Rig availability. Will notify KCC exact date

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR ~~XXXX~~

DATE: 9/1/98 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 3, 1998

Roberts and Murphy, Inc.
PO Box 7125
Shreveport, La. 71137-7125

Petty #1-27
API 15-03320774
SW SE
Sec. 27-34S-20W
Comanche County

Dear Ken Frazier,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888