


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW*SW*" or footage from lines Trego County. Sec. 10 Twp. 12 Rge. 23 (E) W (W)
SW-NE-SE
Lease Owner Beacon Resources Corporation
Lease Name Bender Well No. 1
Office Address 412 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-1 19 67
Application for plugging filed 12-1 19 67
Application for plugging approved 12-1 19 67
Plugging commenced 12-1 19 67
Plugging completed 12-1 19 67
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	160'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug was set at 1210' with 100 sacks cement
Second plug was set at 180' with 20 sacks cement
Third plug was set at 40', solid plug, with 1 sack hulls and 10 sacks cement
Cemented to bottom of cellar

DEC 8 1967
12-08-1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

I SUBSCRIBED AND SWORN to before me this 6th day of December, 19 67



Joseph A. Hess
JOSEPH A. HESS Notary Public.

My commission expires September 19, 1970

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

15-195-20054-00-00

WELL LOG

Company	Beacon Resources Corporation 412 Union Center Wichita, Kansas 67202	Sec. 10-	Twp. 12	Rng. 23
Farm	Bender No. #1	Location	SW-NE-SE	
Total Depth	1945'	County	Trego	
Comm.	11-29-67 Comp. 12-1-67	Elevation:	2450'	K.B.
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		2447'	D. F.
	Casing Record 160' - 8 5/8"	Cement Record 125 sacks cement	2445'	G. R.
			Production:	D & A

Figures Indicate Bottom of Formations

0'	30'	Surface Soil & Clay
30'	140'	Sand & Clay
140'	160'	Shale
160'	850'	Shale
850'	965'	Sand
965'	1230'	Shale
1230'	1392'	Shale & Redbed
1392'	1590'	Sand
1590'	1725'	Shale & Redbed
1725'	1877'	Shale & Redbed
1877'	1924'	Anhy.
1924'	1945'	Shale
1945'	T.D.	

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

RECEIVED
 DEC 8 1967
 12-08-1967
 CONSERVATION DIVISION
 Wichita, Kansas

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Bender #1.

Leo F. Dreiling

 LEO F. DREILING



Subscribed and sworn to before me this 6th day of December 1967.

Joseph A. Hess

 JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970