

15-033-20096-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Comanche County, Sec. 9 Twp. 35S Rge. (E) 20 (W)  
Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Imperial Oil Company  
Lease Name Box Ranch Well No. 128  
Office Address 780 Fourth Nat'l Bldg., Wichita, Ks. RTKCC  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 14, 1971  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced July 14, 1971  
Plugging completed July 14, 1971  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Russell Biberstein of Attica)



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 5625' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	594'	8-5/8"	594'	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 575 Feet,  
Plug and 40 sax Cement; Mud to 80 Feet,  
Bridge and Plug and 20 sax Cement to  
Base of Cellar; 3 sax Cement in Rat Hole  
and 2 sax Cement in Mouse Hole. Job  
Completed @ 7:00 P.M.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Globe Oilwell Cementing, Inc.  
Address Box 628, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Clarence Michael of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael  
500 Bitting Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 1971.

My commission expires November 26, 1974

Louise K. Whitted - Notary Public.

DRILLERS LOGBOX RANCH NO. 1-A

CASING RECORD:	OPERATOR: Imperial Oil Company	DESCRIPTION:
8-5/8" @ 594' w/450 sax cement	CONTRACTOR: Sage Drilling Co.	C NW NE Sec. 9-35S-20W Comanche Co., Kansas
TOTAL DEPTH: 5625'	COMMENCED: July 1, 1971	ELEVATION: 1789KB
	COMPLETED: July 14, 1971	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand	0	40	
Red Bed	40	250	
Red Bed & Shale	250	1000	
Red Bed	1000	1300	
Shale	1300	2135	
Lime & Shale	2135	2335	
Lime	2335	2505	
Lime & Shale	2505	4004	
Shale & Lime	4004	4290	
Lime & Shale	4290	4555	
Lime	4555	4710	
Lime & Shale	4710	4967	
Lime	4967	5058	
Lime & Shale	5058	5262	
Lime	5262	5354	
Lime & Shale	5354	5439	
Lime, Shale & Sand	5439	5490	
Lime	5490	5496	
Sand	5496	5510	
Lime	5510	5550	
Sand, Lime & Shale	5550	5604	
Sand	5604	5625	D&A


RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael  
Clarence Michael

Subscribed and sworn to before me this 15th day of July, 1971.



Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.