

15-033-20361-0000

RECEIVED

FORM CP-4

PRODUCTION
SEP 22 1980


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Comanche County, Sec. 9 Twp. 35X Rge. 20 E/W
Location as "NE/CNW/SW" or footage from lines
660 FSL 660 FEL

Lease Owner Texas Oil & Gas Co.
Lease Name Box Ranch Well No. A-2
Office Address Suite 300-200 W. Douglas, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry



Locate well correctly on above
Section Plot

Date Well completed 6-21 19 80
Application for plugging filed 8-19 19 80
Application for plugging approved 8-20 19 80
Plugging commenced 9-4- 19 80
Plugging completed 9-16 19 80
Reason for abandonment of well or producing formation
Dry

If a producing well is abandoned, date of last production
No 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5740
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	640	None
				4 1/2	5730	4939

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Plug back 5690
Sand from 5690 to 5600
4 sacks cement 5600 to 5560

Ripped pipe at 4940
Pumped in 8 - Hulls
Pumped in 25 Jell
150 sacks 50-50 POZ - 4% Jel 3% C.C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Richard H. [Signature] (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Richard H. [Signature]
(Address) 17th day of September, 19 80

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 80

[Signature]
Notary Public.

My commission expires April 4, 1982

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1980
CONSERVATION DIVISION
Wichita, Kansas

OPERATOR: Texas Oil & Gas Corp.
 CONTRACTOR: Xplor Drilling Company

COMMENCED: 6-5-80
 COMPLETED: 6-21-80
 CASING RECORD: 8 5/8" @ 640'
 4 1/2" @ 5740'

<u>FORMATION:</u>	<u>FROM</u>	<u>TO</u>
Red Bed	528	1685
Dolo & Shale	1685	2290
Shale	2290	2680
Dolo & Shale	2680	3585
Lime & Shale	3585	4855
Shale	4855	4880
Lime & Shale	4880	5740

RECEIVED
 STATE CORPORATION COMMISSION

AUG 25 1980

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I certify that this is a true and correct copy of the Driller's Log on the well drilled 660' FSL - 660 FEL, Sec. 9-35-20, Comanche Cty, Kansas to the best of my knowledge and belief.

XPLOR DRILLING COMPANY

Kirby C. Evers
 Kirby C. Evers, Vice President

Subscribed and sworn to before me this 23rd day of June, 1980.

MY APPOINTMENT EXPIRES NOV 20, 1980
 My appointment expires: