

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

LEASE OPERATOR Roberts + Murphy Inc.

SPOT LOCATION \_\_\_\_\_

ADDRESS PO Box 7125

SEC. 2 TWP. 35S S. RGE 20 (E) of (W)

CITY, STATE, ZIP Shreveport, La. 71137-7125

COUNTY Comanche

PHONE# (318) 221-8601 OPERATORS LICENSE NO. 4145

Date Well Completed \_\_\_\_\_

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 5-23-96

Date Plugging Completed 6-4-96

The plugging proposal was approved on June 3-1996 (date)

by Steve Pfeifer on loc. for top hole (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) Perfs: 6255-63 Depth to Top PBTD 6408 T.D. 6600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	850'	8 5/8	850'	0
		0	6479'	4 1/2	6479'	4380'
				2 3/8		194jts.

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

5-23-96: Rigged up - pulled and layed down 194 x 2 3/8 tbg.  
5-28-96: Set CIBP at 5250' + 2 sx. cement. Pulled and layed down 103 x 4 1/2 casg.  
6-4-96: Allied on location: Pumped 300# hulls - 10sx. gel - 50sx. cement - 10sx. gel - 100# hulls - released plug - 150sx. cement. 60/40 poz - 6 7/8. SIP. 400#.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Roberts + Murphy Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of Plugging contractor of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO PWS, Inc.

SUBSCRIBED AND SWORN TO before me this 7th day of June, 1996

Kenneth W. Furgason  
Notary Public

My Commission Expires: 7-27-96

