

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 209 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 033-20,708-0000

LEASE NAME BOX RANCH

WELL NUMBER 2-11

1825 Ft. from S Section Line

3580 Ft. from E Section Line

SEC. 11 TWP. 35S RGE. 20 ~~0000~~ (W)

COUNTY Comanche

Date Well Completed \_\_\_\_\_

Plugging Commenced Oct. 7, 1994

Plugging Completed Oct. 11, 1994

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR ROBERTS & MURPHY, INC.

ADDRESS P O Box 7125 Shreveport, La. 71137-7125

PHONE#(318) 221-8601 OPERATORS LICENSE NO. 4145

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Oct. 6, 1994 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top Bottom T.D. 5950

Show depth and thickness of all water, oil and gas formations. Perfs: 5328-52; 5378-5404; CIBP 5310;  
 Perfs: 5284-90

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	875	8 5/8	875	0
		0	5950	5 1/2	5950	3520 77its.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Set CIBP at 5250, dumped 2 sx. cement on top. Shot off casing at 3520, pulled & layed down. Top hole plug: 300# hulls, 10 sx. gel, 50 sx. cement, 100# hulls, 10 sx. gel, 8 5/8 plug, 125 sx. cement. 60-40 poz, 6% gel. Max pressure 600#; 300# shut in pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address ROBERTS & MURPHY, INC.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ROBERTS & MURPHY


STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY (Employee ~~XXXXXXXXXXXX~~ Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PRATT WELL SERVICE, INC.



SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 94

Corothy M. Ferguson  
 Notary Public

My Commission Expires February 6, 1997

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-17-94  
 OCT 18 1994  
 COMMISSION DIVISION  
 WICHITA, KANSAS