

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-033-00106-0001

Comanche County, Sec. 3 Twp. 35S Rge. 20 (E) (W)

NORTH

	X		

Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NE NW
Lease Owner Union Oil Company of California
Lease Name J. E. Alexander Well No. 1
Office Address 1812 First Natl. Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5 p.m. 9/14 1959
Application for plugging filed 9/14 1959
Application for plugging approved 19
Plugging commenced 10 a.m. 9/13 1959
Plugging completed 5 p.m. 9/14 1959
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production == 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp - Stafford, Kansas
Producing formation None Depth to top -- Bottom -- Total Depth of Well 6916 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Fresh Water				13-3/8"	520'	None
Salt & Anhydrite				8-5/8"	2481'	1878'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 2521 feet to 2421 feet for each plug set.

Hole filled to surface w/mud. Ran 4 1/2" drill pipe open ended to 2521'.
Halliburton equalized cement plug from 2521' to 2421'. Ran drill pipe open ended to 570'. Halliburton equalized cement plug from 570' to 470'.
Placed 35' cement plug in top of 13-3/8" casing. Welded plate on top of 13-3/8" casing.

RECEIVED
STATE CORPORATION COMMISSION
9-16-59
SEP 16 1959
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Falcon Seaboard Drilling Co.
Address Stanolind Building, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
George T. Murchison (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George T. Murchison
1812 First Natl. Bldg., Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of September, 1959

My commission expires May 17, 1961
Mary Cobb Notary Public.

PLUGGING

File Sec. 3 T 35 R 20E

Book Page 3 Line 31