

API NUMBER 15-033-20-726  
 LEASE NAME Box Ranch  
 WELL NUMBER 4-3

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

870 Ft. from S/W Line of Section (circle one)  
2200 Ft. from E/W Line of Section (circle one)

EASE OPERATOR Roberts & Murphy Inc.  
 ADDRESS P.O. Box 7125  
 CITY, STATE, ZIP Shreveport LA 71137-7125  
 PHONE# (318) 221-8601 OPERATORS LICENSE NO. 4145  
 Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION NW-NE  
 SEC. 3 TWP. 35 S. RGE 20 or (W)  
 COUNTY Comanche  
 Date Well Completed \_\_\_\_\_  
 Date Plugging Commenced June 10, 1997  
 Date Plugging Completed June 17, 1997

The plugging proposal was approved on 6-12-1997 (date)  
 by Richard Lacey (KCC District Agent's Name)  
 Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6500  
 Show depth and thickness of all water, oil and gas formations. P.B.T.D.: 6364 PERFS: 6207.2

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT (What was put in when drilled)	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Pipe	0	666	8 5/8	666'	0
	Casing	0	6436	4 1/2	6436'	4195'
	Rods (7/8-3/4)			3/4-7/8	62 x 7/8 x 186 x 3/4	Same
	Tubing			2 7/8	189' ts.	Same

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

6-10-97 M I R U - 6-11-97 pulled pumps rods & tubing 6-12-97 - Dia log set plug at 6000' - 1st run was misfire, plug set on 2nd run. Cemented top of plug. Ran free point, shot off at 4175 total 98 joints. Riggged down & moved off.  
 (see back for Plugging order)  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PWS, Inc

License No. 5893  
 Address Box 847 Pratt, Ks

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Roberts & Murphy Inc

STATE OF Kans COUNTY OF Pratt

Stephen Hart (Employee of Plugging Contractor of above-described well, being first

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen Hart  
 (Address) C/O PWS 7th

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 97

My Commission Expires: 06/19/00  
 Notary Public Kenneth W. Furgason  
 KENNETH W. FURGASON  
 Notary Public - State of Kansas  
 My Appl. Expires 06/19/00

6.17.97. Allied cement pumped 300# hulls, 10 gal,  
50sx cement, 10 sx gel, 100# hulls, 150sx cement,  
60/40 poz, 6% gel.

6.19.97. Top of cement 209' down from surface.  
State ordered 3 yds cement to fill to surface.