


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Trego County. Sec. 16 Twp. 12 Rge. 23 (E) W (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines S 1/2 SE 1/4
Lease Owner Permian Mud Service Inc., et al
Lease Name Elliott Well No. #1
Office Address Odesa, Texas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed October 30 19 52
Application for plugging filed October 30 19 52
Application for plugging approved October 30 19 52
Plugging commenced October 30 19 52
Plugging completed October 30 19 52
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4050 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	200'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 195', set plug at 195' with 1/2 sack hulls and 15 sacks cement set second plug at 40' with 1/2 sack hulls and 10 sacks cement, cemented to top of pipe.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Glenn R. Nye Drilling Company
Address

STATE OF Kansas, COUNTY OF Ellis, ss.
Glenn R. Nye (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn R. Nye

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of Nov. 1952

My commission expires May 9, 1953

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC 16 T 12 R 234
BOOK PAGE 56 LINE 25

NOV 12 1952
11-12-1952
CONSERVATION DIVISION
Wichita, Kansas

Company: Permian Mud Service Inc. ET AL Farm: Elliott #1
 Contractor: Glenn R. Nye Drilling Company Location: S 1/2 SE 1/4 Sec. 16-12-23
 Commenced: October 13, 1952 Trego County, Kansas
 Completed: October 30, 1952 Casing Record: 8 5/8" set at 200'
 Dry and abandoned

(Figures below indicate bottoms)

cellar	5
surface clay & post rock	45
sand & gravel	155
blue shale	200
shale	300
shale	775
shale & sand	1180
shale & red bed	1435
sand & shale	1630
red bed & shale	1650
red bed & shale	1920
anhydrite	1950
anhydrite	1958
shale & red bed	2120
shale & shells	2263
shale & shells	2465
shale & shells	2550
shale & lime streaks	2685
lime & shale	2790
lime & shale	2860
lime & shale	3000
shale & lime	3125
shale & lime	3185
lime & shale	3255
lime & shale	3488
lime & shale	3465
lime & shale	3565
lime & shale	3632
lime & shale	3690
lime & shale	3760
lime & shale	3771
lime	3805 Kansas City 3805
lime	3835
lime	3863
lime	3900
lime	3950
lime	3983
lime	4025
lime	4050 T.D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

STATE OF KANSAS)
) SS
 ELLIS COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 3rd day of Nov., 1952.



John L. Spiss
 NOTARY PUBLIC

My Commission Expires, May 9, 1953

PLUGGING
 FILE SEC 14 T 12 R 22
 SINK HOLE 56 LINE 25

NOV - 6 1952
 11-06-1952
 CONSERVATION DIVISION
 Topeka, Kansas