

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 12 TWP. 16S RGE. 14W E/W
Location as in quarters or footage from lines:
NE SW NE

Locate Well
correctly on above
Section Platt.

Lease Owner Midwestern Supply Company
Lease Name Hoffman #1 Well No. _____
Office Address 300 Patton Road Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6-10-82
Plugging completed 6-18-82
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 3334'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	314'	none
				5-1/2"	3331'	2219'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 2950' and ran 5 sacks cement. Shot casing @2750',
2630', 2410', 2301' and 2225'. Pulled a total of 61 joints of 5-1/2" casing. Plugged
well with 4 sacks hulls, 20 sacks gel, 8-5/8" plug, 150 sacks 50/50 pos, 4% gel, 3% cc.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 19 82



[Signature]
Notary Public.

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1982
Wichita, Kansas

06-30-82

Schlumberger

SIMULTANEOUS
COMPENSATED NEUTRON-
FORMATION DENSITY

COUNTY BARTON	FIELD TRAPP	LOCATION SEC. 12-16S-14W	WELL HOFFMAN NO. 1	COMPANY INDEPENDENT PROD.	COMPANY INDEPENDENT PRODUCERS, INC.				15-009-22100-00-00			
					WELL HOFFMAN NO. 1							
					FIELD TRAPP							
					COUNTY BARTON				STATE KANSAS			
					LOCATION NE-SW-NE				Other Services: DLL-GR			
API SERIAL NO.		SEC.	TWP.	RANGE								
		12	16S	14W								
Permanent Datum: GROUND LEVEL , Elev.: 1889					Elev.: K.B. 1894							
Log Measured From K.B. , 5 Ft. Above Perm. Datum					D.F. 1891							
Drilling Measured From K.B.					G.I. 1889							
Date	9-30-80											
Run No.	ONE											
Depth-Driller	3334											
Depth-Logger	3333											
Btm. Log Interval	3333											
Top Log Interval	850											
Casing-Driller	8 5/8 @ 314			@		@		@				
Casing-Logger	316											
Bit Size	7 7/8											
Type Fluid in Hole	SALT MUD			RECEIVED								
Dens.	Visc.	9.9		40								
pH	Fluid Loss	7.5		14.4 ml		DEC - 4 1980 ml		ml				
Source of Sample	CIRCULATED											
Rm @ Meas. Temp.	78	@ 85 °F			CONSERVATION DIVISION		@ °F	@ °F				
Rmf @ Meas. Temp.	40	@ 85 °F			Wichita@Kansas		@ °F	@ °F				
Rmc @ Meas. Temp.		@ °F			@ °F		@ °F	@ °F				
Source: Rmf	Rmc	M										
Rm @ BHT	66	@ 98 °F			@ °F		@ °F	@ °F				
TIME	Circulation Stopped	1 000										
	Logger on Bottom	1 300										
	Max. Rec. Temp.	66	98 °F			°F		°F				
Equip.	Location	7714		GREAT BEND								
Recorded By	INGRAHAM, FRANKLIN											
Witnessed By	BROWNLESS, CHURCHILL											

Phone 913-483-2627, Russell, Kansas

Phone 316-793-5861, Great Bend, Kansas

15-009-22100-00-00

Phone Plainville 913-434-2812

Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

No 27780

Home Office P. O. Box 31.

Russell, Kansas 67665

Old

Date	6-18-82	Sec.	17	Twp.	16	Range	14	Called Out	9:30 AM	On Location	1100 AM	Job Start		Finish	7
Lease	Hoffman Well No. 1			Location				Succah 3 1/2 W 1/2 S		County	Barton	State	Kan		

Contractor	Kelso	
Type Job	Old hole Plug	
Hole Size	7 7/8	T.D. 3034
Csg. Size	5 1/2	Depth
Tbg. Size		Depth
Drill Pipe		Depth
Tool		Depth
Cement Left in Csg.		Shoe Joint
Press Max.		Minimum
Meas Line		Displace
Perf.		

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Charge To	Midwestern Supply Co	
Street	300 Patton Rd	
City	GT Bend	State Kan 67520
The above was done to satisfaction and supervision of owner agent or contractor.		

Purchase Order No.	
CEMENT	

Amount Ordered	150 2 1/2" 4 1/2" gal 3/4" acc	
Consisting of	20 sand 4 holes	
Common	75	475
Poz. Mix	75	185
Gel.	26	625
Chloride	4	20.00
Quickset		
Halls	4	14.00

EQUIPMENT

Pumptrk	No	Cementer	WESTON
	63	Helper	DOOS
Pumptrk	No	Cementer	
		Helper	
Bulktrk	134	Driver	RUB
Bulktrk		Driver	TRUM

Handling	184	90
Mileage	27	66
Sub Total		
Total		

DEPTH of Job		
Reference:	Pump Truck	340.00
	Plus	10.00
	27 Mileage 1.50	27.00
	Sub Total	
	Tax	
	Total	377.00

Floating Equipment

Remarks: 4 Holes 25 cement 20 gal Redwood Plus 125 cement

Shipping Pressure 70 Chlorine

Thank You