

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
20D Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15--33-20781

LEASE NAME MILLER

WELL NUMBER 1-28

1700 Ft. from N Section Line

1250 Ft. from E Section Line

SEC. 28 TWP. 34S RGE. 20 or (W)

COUNTY COMANCHE

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-1-92

Plugging Completed 12-22-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ROBERTS & MURPHY, INC.

ADDRESS P O BOX 7125 SHREVEPORT, LA 71137-7125

PHONE#(318) 221-8601 OPERATORS LICENSE NO. 4145

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-21-92 (date)

by DODGE CITY OFFICE, STEVE MIDDLETON ON LOCATION FOR TOP HOLE (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top Bottom PBD: 5474 T.D. 6884

Show depth and thickness of all water, oil and gas formations. PERFS: 5330-32.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	5332	2 3/8	168 jts.	168 jts.
		0	5528	4 1/2	5528 ft.	4880 ft, 116 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

DEC 1: RIGGED UP, PULLED TUBING. DEC. 17: FINISHED PULLING TUBING & MODEL A PACKER.

DEC. 18: PULLED 116 JTS OF 4 1/2 CASING. 4880 FT. FOR PLUGGING: SET CIBP AT 5250 FT, WITH

2 SX CEMENT ON TOP OF PLUG. SHOT OFF AT 4880 FT. TOP HOLE PLUG BY PUMPING 300# HULLS, 10

SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8 PLUG, 150 SX CEMENT. 60-40 POZ,

6% GEL. MAX. 500# SHUT IN: 400#.

(If additional description is necessary, use back of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ROBERTS & MURPHY, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


DEC 29 1992  
12-29-1992

JUDY BERRY (Employee of Plugging Contractor)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) 90 P.W.S. Inc.



SUBSCRIBED AND SWORN TO before me this 28th day of December, 1992

Dorothy M. Furgason  
Notary Public

My Commission Expires February 6, 1993