

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-033-20774-00-00  
API NUMBER 15-033-20774

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Petty  
WELL NUMBER 1-27  
660 Ft. from S Section Line  
2300 Ft. from E Section Line  
SEC. 27 TWP. 35S RGE. 20 (E) or (W)  
COUNTY Comanche  
Date Well Completed 12/12/89  
Plugging Commenced 09/25/98  
Plugging Completed 10/08/98

LEASE OPERATOR Roberts and Murphy, Inc.  
ADDRESS Post Office Box 7125 Shreveport, LA 71137-7125  
PHONE# (318) 221-8601 OPERATORS LICENSE NO. 4145  
Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 3, 1998 (date)  
by David P. Williams (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Pawnee Perf 5012-21 Depth to Top 5000 Bottom 5041 T.O. 6500'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
		0	651'	8 5/8"	651'	0
		0	6500'	4 1/2"	6500'	3896'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Set CIBP @ 4990' & dump bailed 2 sxs cmt on top of CIBP. Cut 4 1/2 csg @ 3896' & pulled out.  
Pumped down 8 5/8 csg: 300# Hulls; 10 sxs gel; 50 sxs cmt; 10 sxs gel; 100# Hulls; 150 sxs cmt (60/40 poz mix, 6% gel). Dumped cmt down 8 5/8 from surface to 10 ft.

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893  
Address Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Roberts and Murphy, Inc.  
Parish  
STATE OF Louisiana COUNTY OF Caddo, ss.

Ken Frazier (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 7125 Shreveport, LA 71137-7125

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1998

Cindy D. Colquette  
Notary Public  
CINDY D. COLQUETTE  
NOTARY PUBLIC IN AND FOR CADDO PARISH  
MY COMMISSION IS FOR LIFE  
My Commission Expires: With Life

10-26-1998