

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-31122-00-00
Spot: NENESE Sec/Twnshp/Rge: 26-11S-21W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: BAUGHER Well #: 1
County: TREGO Total Vertical Depth: 3686 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3686		
SURF	8.625	200	0	150 SX
PROD	5.5	3881	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2010 10:00 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (785) 731-5615

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
BP at 3686'. Perfs at 3601' to 3642'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2010 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 5 1/2" - pumped 340 sxs cement with 500# hulls - full - shut in.
Tied onto backside - pumped 15 sxs cement - shut in.
Max. P.S.I. 100#. Full.

Perfs:

Top	Bot	Thru	Comments
3601	3642		

INVOICED
DATE 4/29/10
INV NO. 2010010234

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3858.

Plugged through: CSG

District: 04

Signed

M. Mills
RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

APR 26 2010

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

APR 22 2010

V & HOUSTON

#1

BAUGHER

26-11-21W
NE NE SE

TOOLS

TREGO

County

STATE P-105 BOPD & 25%WTR
GR 33⁰, LANS 3601-42

B. Comm. _____ Comp. 8/30/62

IP GRP- 240 BOPD/ARB LM

Depth	Datum
3313	-1020
3523	-1230
3547	-1254
3561	-1268
3879	-1586
3886	-1593

Casing 3638-42:
 8" 200
 5" 3881
 WAS SAME OPR: ARB PROD 1/26/62:
 DST 3464-3510/1 HR, 70' M, 100' WTRY M, BHP 1220-1210#:
 DST 3583-3615/ 1 HR, 90' MCO, 90' FROTHY & GCO, 540' GSY O, BHP 925-910#:
 DST 3626-56/30", 60' OCM, 240' MDY O, 680' FR O, 90' O & GCM, 180' OGW, BHP 900-885#:
 DST 3881-86/1 HR, 2010' GL O; 240' HO & GCM, NO WTR, BHP 1140-1140#; CO TD 3886: FU 2800' O/1 HR: SWB 25 BOPD/4HRS, NATL, NH:
 WALTZ NEW INEQ: PERF 16/3638-42, SHO OIL, NATL, ACID 1500: SWB 28 BFPH (50% OIL) PERF 16/3601-05: ACID 1500: SWB 35 BFPH (15% WTR)

DEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS