

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21020-00-01
Spot: S2SENESEW Sec/Twnshp/Rge: 12-28S-16W
1528 feet from S Section Line, 3048 feet from E Section Line
Lease Name: WELLSFORD TOWNSITE OW Well #: 3
County: KIOWA Total Vertical Depth: 4810 feet

Operator License No.: 31739 •
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	469		
PLG		4706		
PROD	4.5	4749	0	WITH 300 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/08/2010 10:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0995

Proposed Plugging Method: SET RETAINER @ 4650'. PUMP 150 SX CMT THROUGH RETAINER. STING OUT OF RETAINER & SPOT 10 SX CMT ON TOP OF RETAINER. PERFORATE @ 1220' & 500'. RUN TBG & PACKER SPOT 50 SX CMT THROUGH PERFS AT 1220'. PULL PACKER TO 490' & CIRCULATE CMT TO SURFACE THROUGH PERFS @ 500'.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL
Date/Time Plugging Completed: 04/08/2010 2:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET RETAINER @ 4640'. LOADED TBG WITH CMT AND STUNG INTO RETAINER. PUMPED 15 SX CMT THROUGH RETAINER. PRESSURED TO 1000 PSIG & HELD 1000 PSIG. STUNG OUT OF RETAINER & DISPLACED 25 SX CMT ON TOP OF RETAINER. PULLED TBG TO 1222'. PUMPED 50 SX CMT. HAD GOOD RETURNS UP 4 1/2" AND 8 5/8" X 4 1/2" ANNULUS. PULLED TBG TO 505'. PUMPED 180 SX CMT. CIRCULATED CMT TO SURFACE UP 4 1/2" & 8 5/8" X 4 1/2" ANNULUS. PULLED TBG OUT OF HOLE. TOPPED WELL OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4677	4681		

INVOICED
DATE 4/29/10
INV. NO. 2010010236

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED

APR 19 2010

KCC DODGE CITY

APR 26 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-243