

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10007-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 29-32S-43W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MOHLER CU Well #: 1
County: MORTON Total Vertical Depth: 3362 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3145		
SURF	8.625	681		WITH 350 SX CMT
PROD	5.5	3358	800	WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/09/2010 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 1. MIRU WSU. UNSEAT PUMP & POOH W/ RODS & PUMP. NU BOP. PUMP 20 BLS. MUD AHEAD & MIX & SPOT 40 SXS CI C CMT. W/ COTTON SEED HULLS UP TO 2711'. POOH W/ TBG & WOC. 2. TAG TOC. LOAD CSG. W/ MUD. 3. CUT & PULL FREE PIPE. 4. TIH W/ TBG. @ 781' & SPOT 100 SXS CI C CMT UP TO 412'. 5. TOP OUT FROM 54' - 4' W/ 15 SXS CMT. 6. CUT OFF 4' BELOW GL. WELD ON ID PLATE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE
Date/Time Plugging Completed: 04/09/2010 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 100# HULLS & 40 SX CMT AT 3090'. 1ST PLUG AT 1410' WITH 40 SX CMT. 2ND PLUG AT 731' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 30 SX CMT. 4TH PLUG AT 50' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3244	3250		
3227	3232		
3204	3210		
3112	3120		
3102	3112		
3092	3102		

INVOICED
DATE 4/29/10
INV. NO. 2010010238

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

APR 19 2010

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

APR 26 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-203