

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15525-00-00
Spot: SENENE Sec/Twnshp/Rge: 31-19S-12W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: KOHLER Well #: 11
County: BARTON Total Vertical Depth: 3990 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	180	0	150 SX
PROD	5.5	3388	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2010 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: L.D. DAVIS Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 250# hulls.
Perf: 475' - 750' - 1400'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2010 11:15 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 1580' - pumped 300 sxs cement with 250# hulls - cement circulated.
POOH. Hooked up to casing and pumped 60 sxs cement.
Max. P.S.I. 100#.
Cement circulated out the Braden head.

INVOICED
DATE 4/29/10
INV. NO. 2010010240

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36502.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
RECEIVED
KANSAS CORPORATION COMMISSION (TECHNICIAN) CM

APR 26 2010

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

APR 21 2010

W. L. HARTMAN

#11 KOHLER

31-19-12W 53
SE NE NE

Contr. H & H DRILLING COMPANY BARTON County

E 1821 Comm. _____ Comp. 7-18-52 IP 487 BOPD
PHY POT.

Tops	Depth	Datum	Casing
HEEB	2984	-1163	8" 180 5" 3388 ACID 1000
LANS	3114	-1293	
ARB	3387	-1566	
TD	3990	-1569	

FT. ZARAH POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS