

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04352-00-00
Spot: NWNESE Sec/Twnshp/Rge: 4-18S-14W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: MONROE Well #: 6
County: BARTON Total Vertical Depth: 3427 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	889	0	325 SX
COND	13.38	254	0	225 SX
PROD	6	3398	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2010 7:45 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING COMPANY Phone: (620) 793-2168

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 600# hulls - 15 sxs gel.
Perf: 805' - 205'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2010 12:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3292' - pumped 15 sxs gel - followed with 75 sxs cement with 200# hulls.
Pulled tubing to 1458' - pumped 200 sxs cement with 400# hulls - cement circulated.
POOH. Hooked up and pumped 10 sxs cement.
Shut in at 200# P.S.I.
Cellar and Braden head were full of cement.

Perfs:

Top	Bot	Thru	Comments
3398	3427		ARBUCKLE
3306	3310		LKC 'H'
3178	3181		LKC 'A'

INVOICED
DATE 4/29/10
INV. NO. 20100810242

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3814.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

RECEIVED
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 26 2010

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

APR 21 2010

CONTINENTAL & PHILLIPS #6 MONROE

52 4-18-14W
NW NE SE

Contr. _____ BARTON _____ County

E 1931 Comm. _____ Comp. 5-5-50 IP 165 BOPD


Tops	Depth	Datum
ANH	881	+1050
HEEB	3100	-1169
LANS	3179	-1248
CHTY CONG	3386	-1455
ARB	3397	-1466
TD	3408	-1477

Casing

13" 254
 9" 889
 6" 3398

ACID 500: SWB 6 BOPH/
 12 HRS.

BOYD POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS