

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04354-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 4-18S-14W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MONROE Well #: 8
County: BARTON Total Vertical Depth: 3485 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3463		
SURF	8.625	278	0	175 SX
DVT		3463		
PROD	5.5	3484	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2010 9:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: THOMAS LARSON Company: LARSON OPERATING COMPANY Phone: (620) 793-2168

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 600# hulls.
Junk in the hole at 2400' - will plug.
Perfed 1640'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2010 11:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 2400' - tied to tubing - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1640' - pumped 140 sxs cement with 250# hulls - circulated cement to surface on casing.
Pulled tubing - tied to casing - pumped 15 sxs cement.
Max. P.S.I. 400#.
Tied to backside surface pressured to 500# P.S.I. Shut in - full.

Perfs:

Top	Bot	Thru	Comments
3470	3473		ARBUCKLE
3433	3439		ARBUCKLE

INVOICED
DATE 4/29/10
INV. NO. 2010010242

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
RECEIVED (TECHNICIAN) CM
KANSAS CORPORATION COMMISSION

APR 26 2010

Form CP-2/3

APR 21 2010

CONSERVATION DIVISION
WICHITA, KS

Contr. LOHMANN & JOHNSON BARTON County

E 1951^{RB} Comm. _____ Comp. 6-29-56 IP 60 BOPD

Tops	Depth	Datum
TOP	2892	-941
HEEB	3131	-1180
BR LM	3198	-1247
LANS	3210	-1259
CONG	3412	-1461
ARB	3431	-1480
TD	3485	-1534

Casing

8" 278


5" 3484

PERF 3470-73: WTR: PB: PERF

3433-39: ACID 200: 9 B0 & 5

BWPH

BOYD POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS