

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23010-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 4-18S-14W  
2330 feet from S Section Line, 335 feet from E Section Line  
Lease Name: R MONROE Well #: 10  
County: BARTON Total Vertical Depth: 3660 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3280		
SURF	8.625	184	0	150 SX
PROD	5.5	3447	0	300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/15/2010 2:00 PM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING COMPANY Phone: (620) 793-2168

Proposed Plugging Method: Ordered 210 sxs 60/40 pozmix - 4% gel - 600# hulls - 16 sxs gel.  
Perfed at 1250'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/15/2010 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3260' - tied to tubing and pumped 16 sxs gel - followed with 50 sxs cement and 100# hulls.  
Pulled tubing to 1250' - pumped 165 sxs cement with 250# hulls - circulated cement to surface on casing.  
Pulled tubing - tied to casing - pumped 15 sxs cement.  
Max. P.S.I. 450#.  
Topped off backside surface with 14 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3384	3401		
3296	3302		
3229	3231		
3188	3190		
3160	3164		

NVOICED  
DATE 4/29/10  
TRV. NO. 2010010242

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 26 2010

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS


APR 21 2010

REPLACEMENT CARD

ENERGY RESERVES GROUP, INC. 4-18-14W  
 925 PATTON ROAD #10 R. MONROE NE NE SE

GREAT BEND, KS 67530  
 CONTR SALWSON DRLG. CO., INC. CTY BARTON

GEOL \_\_\_\_\_ FIELD BOYD



ELV 1913 KB SPD 12/30/82 <sup>CARD</sup>ISSUED 3/3/83 IP P 99 BOPD, NW  
 LKC 3160-3302 OA  
 API 15-009-23,010 ARB 3385-3401

LOG	Tops	Depth/Datum
ANH	863	1050
TOP	2842	929
HEEB	3082	1169
TOR	3090	1177
BR LM	3152	1239
LANS	3157	1244
BKC	3363	1450
ARB	3377	1464
COLORLESS QUARTZITE		
	3547	1634
GRAN WSH		ABSENT
RTD		3661-1748

8 5/8 " 184/150 SX; 5 1/2 " 3447/300 SX; DV TOOL AT 876/180 SX  
 NO DST'S  
 MICT - CO, PF (ARB) 3399-3401 & 3385-89, SWB DWN, GSO,  
 AC 1000 G, PF (LKC H) 3296-3302 & (LKC A) 3160-64, SWB LD,  
 GSO, R & T, POP, P 99 BOPD, NW 1/30/83 COMMINGLED

CORRECTION: 12/15/83 - CORRECTED LOWER HOLE TOPS - WAS REAG 3547 & GRAN WSH 3591  
 NOTE: 2/10/83 - ORIGINALLY FIRST REPORTED AS #2 BO POOL 'SWD'