

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21815-00-00  
Spot: SENENE Sec/Twnshp/Rge: 23-18S-8W  
4349 feet from S Section Line, 332 feet from E Section Line  
Lease Name: WILLMS Well #: 1  
County: RICE Total Vertical Depth: 3244 feet

Operator License No.: 8653  
Op Name: PETROLEUM TECHNOLOGIES, INC.  
Address: 801 W 47TH ST STE 412  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	243		175 SX
PROD	5.5	3243		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2010 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/06/2010 10:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3080' AND CAP WITH 5 SX'S CEMENT. PERFORATE @ 1100', 750' AND 293'. RUN TUBING TO 1100' AND PUMP 35 SX'S CEMENT WITH CIRCULATION. PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT WITH CIRCULATION. PULL TUBING TO 293' AND STARTED CIRCULATION--BUT LOST. COME BACK ON 4-6-10 AND TAGGED CEMENT @ NEAR 1100'. RUN TUBING BACK DOWN TO 1100' AND PUMP 35 SX'S CEMENT WITH CIRC. PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT WITH CIRC. PULL TUBING TO 293' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND PUMP 20 SX'S ON BACKSIDE UP TO 300#'S--HELD PRESSURE. TOP OFF CASING. USED 380 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3160	3163		

INVOICED  
DATE 4/29/10  
INV. NO 2010010245

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #6029. COPELAND TICKET C-36665.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 20 2010

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KANSAS

JK